

Tender No. 20/2014-15/NGS

| Name of work: SUPPLYING AND LAYING R.C.C PIPE FOR STORM WATER DRAINAGE FOR THE GAMES VILLAGE AT MENAMKULAM, THIRUVANANTHAPURAM | | | | | | | |
|---|---------|-----|---|----------|--|------|------------|
| RE TENDER SCHEDULE | | | | | | | |
| Sl.No. | Qty | | Description | Rate | | Unit | Amount |
| | | | | In fig. | In words | | |
| 1 | 1350.00 | m3 | Earth work excavation in ordinary soil and depositing on bank with initial lead upto 50m and lift upto 1.5m including breaking clods, watering, ramming and sectioning of spoil bank etc. complete. | 1452.39 | (Rs. One thousand four hundred and fifty two and Ps. Thirty nine only) | 10m3 | 196073.00 |
| 2 | 800.00 | m | Providing and laying non-pressure NP2 class (light duty) RCC pipes of 500 mm dia in 2.50 m length (two pipes in parallel), join together with RCC collars NP2 class 500 mm jointed with stiff mixture of cement mortar in the proportion of 1:2 including testing of joints etc. including all cost conveyance, handling, lowering and placing in position to lines, levels and gradient in trenches already taken including all labour, cost, hire of appliances etc. complete as per direction. | 1500.00 | (Rs. One thousand five hundred only) | m | 1200000.00 |
| 3 | 10 | nos | Constructing manhole of size 1.80x1.80x1.50m (av.) (inside dimension) with solid block masonry using cement concrete blocks 40x20x20 CM in cement mortar 1:6, foundation concrete using 1:4:8 mix with 20 mm broken stone, inside plastering 12 mm thick with cement mortar 1:4 finished with floating coat of neat cement, 15 cm thick RCC cover slab using c.c 1:2:4 mix with 20mm broken stone etc. complete as per standard design and as directed by the Engineer in charge. | 28078.00 | (Rs. Twenty eight thousand and seventy eight only) | E | 280780.00 |
| (Rs. Sixteen lakhs Seventy six thousand Eight hundred and Fifty three only) | | | | | | | |
| 1676853.00 | | | | | | | |

CONTRACTOR

CHIEF ENGINEER

NATIONAL GAMES SECRETARIAT, THIRUVANANTHAPURAM

Name of work:- SUPPLYING AND LAYING R.C.C PIPE FOR STORM WATER DRAINAGE FOR THE GAMES VILLAGE AT MENAMKULAM, THIRUVANANTHAPURAM

I/We agree to carry out the work (1) at estimate rate

(2) at% below the estimate (in figure & words)

(3) at% above the estimate (in figure & words).

** Tender excess/deduction will not be applicable for market rate items in the schedule of contract

Signature of Tenderer

Name.....

Address.....

Contractor

Chief Engineer