

Name of work:- GAMES VILLAGE AT MENAMKULAM- RAISING THE COMPOUND WALL AND PROVIDING FENCING

TENDER SCHEDULE

APPX: A PROVIDING BARBED WIRE FENCING

| Sl.no. | Qty | | Description | Rate Rs. | | Unit | Amount |
|--------|--------|----|--|----------|---|------|-----------|
| | | | | in Fig. | in Words | | |
| 1 | 36.00 | m3 | Earth work excavation in ordinary soil and depositing on bank with initial lead upto 50m and lift upto 1.5m including breaking clods, watering, ramming and sectioning of spoil bank etc. complete. | 1452.39 | Rs. One thousand four hundred and fifty two and Ps. Thirty nine only | 10m3 | 5229.00 |
| 2 | 100.00 | m3 | Masonry work using Concrete hollow blocks 40x20x15cm in cement mortar 1:8 for raising the height of compound wall and re construction of damaged compound wall including cost, conveyance and all other charges. | 4324.73 | Rs. Four thousand three hundred and twenty four and Ps.seventy three only | m3 | 432473.00 |
| 3 | 29.00 | Q | Fabrication supply and fixing post using MS angle iron 45x45x5mm @ 2.00m C/C including cutting to required length, drilling necessary holes, labour and all other charges.etc. complete. | 9586.50 | Rs. Nine thousand five hundred and eighty six and Ps. fifty only | Q | 278009.00 |
| 4 | 18.00 | m3 | Fixing angle iron and G.I post using Plain Cement concrete 1:3:6 using 20mm nominal size broken stone including cost of all materials,labour for mixing, placing, watering, curing etc. complete. | 6590.19 | Rs. Six thousand five hundred and ninety and Ps. nineteen only | m3 | 118623.00 |
| 5 | 900.00 | m2 | Painting with synthetic enamel paint of suitable colour using approved quality paint as specified two coats over priming coat. | 819.95 | Rs. Eight hundred and nineteen and Ps. Ninety five only | 10m2 | 73796.00 |
| 6 | 550.00 | m2 | Plastering with cement mortar 1:4, 12mm thick one coat floated hard and trowelled smooth including cost and conveyance of materials, labour charges etc. complete | 2156.68 | Rs. Two thousand one hundred and fifty six and Ps. Sixty eight only | 10m2 | 118617.00 |

CONTRACTOR

CHIEF ENGINEER

| | | | | | | | |
|---|---------|---|--|--------|---|---|-----------|
| 7 | 600.00 | m | Fabrication supply and fixing 50mm dia B class GI pipe at an interval of 2.00 m c/c in foundation of size 45x45x60 cm in cement concrete 1:4:8 using 20 mm broken stone including cutting pipe into required length of 3 m, sealing the top with 2mm thick circular plate welding, cutting and bending to 30° at 0.50m from the top, painting with two coats of synthetic enamel paint of approved quality after a coat of zinchromat primer etc. complete including cost conveyance and all other charges etc. complete as per direction of Engineer in charge. | 388.00 | Rs. Three hundred and eighty eight only | m | 232800.00 |
| 8 | 1500.00 | m | Fencing with G.I 2 strand barbed wire (No. 12x12 gauge @ 0.154kg/m) in 5 lines horizontally and 2 lines diagonally , fixing/tying rigidly with staples to post already fixed at 2.0m apart etc. complete as per direction. | 83.00 | Rs. Eighty three only | m | 124500.00 |

APPX: B PROVIDING CHAIN LINK FENCING

| | | | | | | | |
|---|--------|-----|---|---------|---|----|-----------|
| 1 | 151 | nos | Fabrication supply and fixing 50mm dia B class GI pipe at an interval of 2.00 m c/c in foundation of size 45x45x75 cm in cement concrete 1:4:8 using 20 mm broken stone including cutting pipe into required length of 3 m, sealing the top with 2mm thick circular plate welding, cutting and sizing 25x6mm MS flat for fixing chain link, drilling suitable size holes in pipe and flat for bolts, supply of bolts,nuts and washers etc. complete including painting with two coats of synthetic enamel paint of approved quality after a coat of zinchromat primer etc. complete including cost conveyance and all other charges etc. complete as per direction of Engineer in charge. (Earth work and concrete will be measured seperately) | 1370.42 | Rs. One thousand three hundred and seventy and Ps. Fourty two only | E | 206933.00 |
| 2 | 23.00 | M3 | Cement concrete 1:4:8 using 20mm nominal size broken stone including fixing the post in position to lines and levels including conveying, placing concrete, ramming, watering, curing etc. complete. | 6197.37 | Rs. Six thousand one hundred and ninety seven and Ps. Thirty seven only | m3 | 142540.00 |
| 3 | 720.00 | M2 | Providing and fixing GI chain link fabric fencing of 2.4m width in mesh size 50x50mm made of GI wire of 4mm, PVC coated to achieve outer dia not less than 5mm in required colour and shade, including fixing firmly with pipe post with MS flat using bolts, nuts, washers etc.complete as per direction of Engineer in charge. | 688.85 | Rs. Six hundred and eighty eight and Ps. Eighty five only | m2 | 495972.00 |

PAC Rs. **22,29,492.00**

(Rs. Twenty two lakhs twenty nine thousand four hundred and ninety two only)

CONTRACTOR

CHIEF ENGINEER

NATIONAL GAMES SECRETARIAT, THIRUVANANTHAPURAM

Name of work:- GAMES VILLAGE AT MENAMKULAM- RAISING THE COMPOUND WALL AND PROVIDING FENCING

I/We agree to carry out the work (1) at estimate rate

(2) at% below the estimate (in figure & words)

(3) at.....% above the estimate (in figure & words).

** Tender excess/deduction will not be applicable for market rate items in the schedule of contract

Signature of Tenderer

Name.....

Address.....