

NATIONAL GAMES SECRETARIAT

NAME OF WORK:- Providing chain link fencing around the play ground at Mount Tabor School, Pathanapuram, Kollam.

TENDER SCHEDULE :- ABSTRACT

Description	Amount (Rs.)
Civil Works	265000
Grand total	265000

(Two Lakhs Sixty Five Thousand only)

I/We agree to carry out the work at par with estimate(1) at estimate rate.....

(2).....% above the estimate (in figure & words)

(3).....% below the estimate (in figure & words)

Signature of Contractor

Witness

Name.....

Address.....

NATIONAL GAMES SECRETARIAT

**providing chain link fencing around the play ground at Mount Tabor School,
Pathanapuram, Kollam.**


No	Item No	Quantity	Unit	Rate	Amount
1	Earth work in excavation for the foundation trenches by manual means including disposal of excavated earth, lead upto 50 m and lift upto 1.5 m; disposed earth to be levelled and neatly dressed, as directed by the Engineer- in-Charge. (size of pit = 45 x 45 x 60 cms)	8	m ³	291	2328
2	Providing and laying cement concrete of 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) properly mixed and consolidated with hand rammers, including cost and conveyance of all materials, labour, curing, lead lift , etc. complete for all work up to plinth levels as directed by Engineer- in-Charge.	8	m ³	5750	46000
3	Providing and fixing PVC coated GI chain link fencing of height 3.60m with 50x50mm woven net with 2.85 mm dia GI wire +1.15 mm thk PVC coating (total 4mm dia) using 40 mm dia GI pipe as verticals @ 2.40 mts intervals as per drawing. Chain link will be spirally woven netting of 1.8 m height and is fixed to an angle iron frame of ISA 40 x 40 x 4mm using nuts and bolts and the angle frame is fixed to the vertical pipe used as pillars at an interval of 2.4m, and it is fixed in PCC block 1:4:8 of size 450x450x600 mm. The rate includes cost and conveyance of all materials, painting with two coat of anti corrosive yellow zinc chromate primer and two coats of synthetic enamel paint labour charges, lead, lift, etc complete at all levels and as directed by Engineer-in-charge.	150	mts	1378	206700
4	Additional provision for two numbers of gates with chain link fencing		LS		9972
					265000
Say Rupees two lakhs sixty Five thousand only.					

40 MM DIA GI VERTICAL PIPE
240c/c


EQUAL ANGLE 40x40x4mm, 3 numbers

40 MM DIA GI VERTICAL
PIPES @ 240 cms C/C

CHAIN LINK FENCING



360



GROUND LEVEL

GROUND LEVEL

PCC 1:2:4 USING 40 mm
BROKEN STONE

PIT SIZE 45x45x60 cms

60.0

TYPICAL DETAILS OF FENCING

45.0

CONSTRUCTION OF CHAIN LINK FENCING FOR THE STADIUM IN MOUNT
TABOR SCHOOL GROUND AT PATHANAPURAM, KOLLAM