

35th NATIONAL GAMES KERALA

Name of work :- New Hockey Stadium,Asramam Kollam (Additional works)- Earth filling inside the stadium.

SCHEDULE FOR ABSTRACT OF COST

SI No	Description item	Qty	UNIT	Rate in Figure	Rate in Words	Amount (Rs)
1	Supplying of good earth / gravelly earth at site including royalty and necessary from concerned authority up to 40 Km lead and banking the earth in layers not exceeding 20 Cm in depth breaking clods watering, rolling each layers with 0.50 Ton Roller or wooden or steel rammers and rolling every third and top most layer with power roller of minimum 8 Ton to obtain desired density and dressing up all complete. Payment shall be made the rolled and consolidated volume of earth fill.	18000	cum	428.60	Rupees Four Hundred and Twenty Eight and Paise Sixty Only	7,714,800

Estimate PAC :- (Rupees Seventy Seven Lakhs Fourteen Thousand and Eight Hundred Only)

Rs.77,14,800/-

Abstract

Total for Earth Filling - Rs. 7714800/-

Value of PWD SOR item - Rs .7714800/-

TOTAL - Rs. 77,14,800/-

I/We agree to carry out the work

* (1). at estimate rate

* (2). at% above estimate rate (in figure & words).....

* (3). at% below the estimate (in figure & words).....

less cost of departmental materials/ market rate items.

* Note:- Strike out which ever is not applicable.

Tenderer

Chief Engineer