

Name of work : Repainting Works at Corporation stadium, Kozhikode

RE TENDER SCHEDULE

Sl.No.	Qty		Description	Rate		Unit	Amount
				In fig.	In words		
1	37000.00	m2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	11.43	(Rs. Eleven and Ps. Forty Three only)	m2	4,22,910.00
2	37000.00	m2	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats @ 2.20 kg/10 sqm) complete	44.00	(Rs. Forty Four only)	m2	16,28,000.00
3	1200.00	m2	Scraping and cleaning old painted metal surfaces with sand paper etc. including all labour charges..	42.00	(Rs. Forty Two only)	m2	50,400.00
	1200.00	m2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	52.51	(Rs.Fifty Two and Ps. Fifty One only)	m2	63,012.00
							21,64,322.00

(Rs. Twenty One lakhs Sixty Four thousand Three hundred and Twenty Two only)

1. Rate/sqm to be inclusive of all costs and statutory recoveries such as VAT,TDS & KCWWF(1%) to be included
2. Rate to be inclusive of all conveyance charges, labour charges etc complete.

CONTRACTOR

CHIEF ENGINEER

NATIONAL GAMES SECRETARIAT, THIRUVANANTHAPURAM

Name of work:- Repainting Works at Corporation Stadium, Kozhikode

I/We agree to carry out the work (1) at estimate rate

(2) at% below the estimate (in figure & words)

(3) at.....% above the estimate (in figure & words).

** Tender excess/deduction will not be applicable for market rate items in the schedule of contract

Signature of Tenderer

Name.....

Address.....