

## Name of work : Repainting Works at Indoor stadium, Agriculture College, Vellayani, Thiruvananthapuram

## TENDER SCHEDULE

Sl.No.	Qty		Description	Rate		Unit	Amount
				In fig.	In words		
(A)			<b>Front Block</b>				
1	1040.00	m2	Finishing walls with acrylic smooth exterior paint of required shade old work (two or more coats applied @ 1.67lit/10m2) on existing cement paint surface, including scrapping, cleaning and preparing the surface smooth including necessary repairs to scratches etc. complete as directed by the Engineer in charge	78.04	(Rs. Seventy Eight and Ps. Four only)	sq.m	81,162/-
2	1490.00	m2	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade one or more coats on old work, including scrapping, cleaning and preparing the surface smooth including necessary repairs to scratches etc. complete as directed by the Engineer in charge	64.65	(Rs. Sixty four and Ps. Sixty five only)	m2	96,329/-
3	1000.00	m2	White washing with lime to give an even shade old work (two or more coats) including scrapping, cleaning and preparing the surface smooth including necessary repairs to scratches etc. complete as directed by the Engineer in charge	11.80	(Rs. Eleven and Ps. Eighty only)	m2	11,800/-
4	250.00	m2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade. One or more coats on old work including scrapping, cleaning and preparing the surface smooth including necessary repairs to scratches etc. complete as directed by the Engineer in charge	57.06	(Rs. Fifty seven and Ps. Six only)	m2	14,265/-
			<b>Total for (A)</b>				<b>2,03,556/-</b>

			<b>Indoor stadium (Exterior walls and balcony area)</b>				
1	1600.00	m2	Finishing walls with acrylic smooth exterior paint of required shade old work (two or more coats applied @ 1.67lit/m2 on existing cement paint surface including scrapping, cleaning and preparing the surface smooth including necessary repairs to scratches etc. complete as directed by the Engineer in charge	78.04	(Rs. Seventy Eight and Ps. Four only)	sq.m	1,24,864/-
2	1500.00	m2	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade one or more coats on old work including scrapping, cleaning and preparing the surface smooth including necessary repairs to scratches etc. complete as directed by the Engineer in charge	64.65	(Rs. Sixty four and Ps. Sixty five only)	m2	96,975/-
3	260.00	m2	White washing with lime to give an even shade old work (two or more coats) including scrapping, cleaning and preparing the surface smooth including necessary repairs to scratches etc. complete as directed by the Engineer in charge	11.80	(Rs. Eleven and Ps. Eighty only)	m2	3,068/-
	320.00	m2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade. One or more coats on old work including scrapping, cleaning and preparing the surface smooth including necessary repairs to scratches etc. complete as directed by the Engineer in charge	57.06	(Rs. Fifty seven and Ps. Six only)	m2	18,259/-
			Total for (B)				<b>2,43,166/-</b>
			<b>Grand Total (A) +(B)</b>				<b>4,46,722/-</b>
<b>(Rupees Four Lakh Forty Six Thousand Seven Hundred and Twenty Two Only)</b>							
1. Rate/sqm to be inclusive of all costs and statutory recoveries such as VAT, TDS & KCWWF(1%) to be included							
2. Rate to be inclusive of all conveyance charges, labour charges etc complete.							

**NATIONAL GAMES SECRETARIAT, THIRUVANANTHAPURAM**

**Name of work:- Repainting Works at Indoor stadium, Agriculture College, Vellayani, Thiruvananthapuram**

I/We agree to carry out the work (1) at estimate rate .....

(2) at .....% below the estimate (in figure & words)

(3) at.....% above the estimate (in figure & words).

\*\* Tender excess/deduction will not be applicable for market rate items in the schedule of contract

Signature of Tenderer

Name.....

Address.....