

NATIONAL GAMES SECRETARIAT

Name of Work : Upgradation/Renovation of Existing Corporation Stadium, Kollam

SPECIFICATION AND SCHEDULE OF QUANTITIES

Sl.No	Description of Items	Quantity	Unit	Rate in Figures (Rs)	Rate in words	Amount(Rs)
	Appendix-A					
1	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade a)Old work (Two or more coats applied @ 1.43 ltr/ 10 sqm) over existing cement paint surface.	30000	sqm	50.45	Rupees Nine and Paise Fifty Two Only	1513500
2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : a)One or more coats on old work	1700	sqm	45.25	Rupees Fourty Seven and Paise Eighty One Only	76925
3	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade : a)One or more coats on old work.	6000	sqm	51.80	Rupees Fifty Seven and Paise Six Only	310800

4	Providing and Fixing MS framed cantilever bracket with 6mm poly carbonate roof sunshade a) Supply and fixing of 6 mm thick Multiwall Bronze colour with UV protection treatment trade code name, Lexan Metallic Grey LTC 6/2 RS 1.2 SC' of SABIC PLASTICS Sheets, weight not less than 1300 gm/Sqm-Light transmission of 60% for bronze.	75	cum	3,331.20	Rupees Six Thousand Seven Hundred Ninty One and Paise Ninty Five Only	249840
	b) The masking carrying instruction as to which side UV protected & the same side should be installed facing out wards.					
	c) fire retardant confirming to IS 14443-198					
	d) Aluminum Alcox leak proof fixing					
	e) Truss work / cantilever bracket , purlin etc. shall be Tata sections 50 x 25 x 2 mm rect.sect,(TATA STEEL), all complete as per direction of Engineer-In-charge (The rate is inclusive of all materials & labours involved in cluding structural steel work).					

5	Replacing chain link fabric fencing of required width in mesh size 50x50 mm i/c strengthening with 2 mm dia. wire: Made of G.I. of dia. 4 mm. including painting with synthetic Enamel paint two coats over priming coat of Zinc Chromite primer	154	no.	765.10		117825
6	P/F MS grills of required pattern in frames of windows Fixed to openings/wooden frames with rawl plugs screws etc. including painting 2 coats with Synthetic enamel paint over a priming coat of steel primer	500	kg	210.45	Rupees Eight and Paise Sixty Nine Only	105225
7	Applying chemical water proofing treatment of NITO Zone primer to terrace @ 2.50 liter /10sqm after preparing and attending the leak prone crevices with epoxy filling materials , including cleaning the surface etc as per direction of Engineer In Charge	302	job	376.40	Rupees Two Thousand Six Hundred Twenty Seven and Paise Thirty Two Only	113673
TOTAL						2487788

(Rupees Twenty Four Lakh Eighty Seven Thousand Seven Hundred and Eighty Eight)

I / we agree to carry out the work

(1) at estimate rate

at.....% above estimate

at% above estimate r (in figures and words)